

**PRICE PROPOSAL FORM**  
**RFP NO. 2026-006-NP**

All items include costs for furnishing to the City all necessary materials, equipment, and supplies and for all costs incurred in completing the Work, including installation of all materials, services, equipment, and supplies furnished, complete in place and ready for continued service, all other labor, permit fees, taxes, insurance, bonds, and other miscellaneous costs, **overhead and profit**.

General Conditions					
Item No.	Description	Quantity	Unit of Measure	Unit Price	Extended Price
1	Mobilization/Demobilization	1	LS		
2	Insurance and Bonds	1	LS		
3	Maintenance of Traffic (MOT)	1	LS		
4	Audio Video Documentation	1	LS		
5	Project Record Documents	1	LS		
6	Utility Locates	1	LS		
7	NPDES Permit/Environmental and Erosion Control Measures	1	LS		
Water & Sewer					
8	Furnish and Install 4" DIP WM via Open-Cut	440	LF		
9	Furnish and Install 6" DIP WM via Open-Cut	29,540	LF		
10	Furnish and Install 8" DIP WM via Open-Cut	1,810	LF		
11	Furnish and Install 10" DIP WM via Open-Cut	2,250	LF		
12	Furnish and Install 16" DIP WM via Open-Cut	50	LF		
13	Furnish and Install 20" DIP WM via Open-Cut	50	LF		
14	Furnish and Install 24" DIP WM via Open-Cut	50	LF		
15	Furnish and Install 6" DIP FM via Open-Cut	370	LF		
16	Furnish and Install 8" DIP FM via Open-Cut	1,460	LF		
17	Furnish and Install 10" DIP FM via Open-Cut	40	LF		
18	Furnish and Install 14" DIP FM via Open-Cut	50	LF		
19	Furnish and Install 24" DIP FM via Open-Cut	3,880	LF		

<b>Water &amp; Sewer (Cont.)</b>					
<b>20</b>	Furnish and Install 6" DR-11 HDPE FM via HDD	1,270	LF		
<b>21</b>	Furnish and Install Ductile Iron Fittings (Water Main)	7	TON		
<b>22</b>	Furnish and Install Ductile Iron Fittings (Force Main)	7	TON		
<b>23</b>	Investigation and Determination of New Meter Location	205	EA		
<b>24</b>	Furnish and Install 1" Water Meter and Meter Box	531	EA		
<b>25</b>	Furnish and Install 1.5" Water Meter and Meter Box	36	EA		
<b>26</b>	Furnish and Install 2" Water Meter and Meter Box	4	EA		
<b>27</b>	Furnish and Install 1" Dual Check Valve Assembly	150	EA		
<b>28</b>	Furnish and Install 1.5" Dual Check Valve Assembly	10	EA		
<b>29</b>	Furnish and Install 1-inch Meter Setter Assembly	5	EA		
<b>30</b>	Furnish and Install 1.5-inch Meter Setter Assembly	5	EA		
<b>31</b>	Furnish and Install Single Service - Short	164	EA		
<b>32</b>	Furnish and Install Single Service - Long	152	EA		
<b>33</b>	Furnish and Install Double Service - Short	59	EA		
<b>34</b>	Furnish and Install Double Service - Long	65	EA		
<b>35</b>	Furnish and Install Single Service - Long (Cul-de-Sac)	2	EA		
<b>36</b>	Furnish and Install Double Service - Long (Cul-de-Sac)	2	EA		
<b>37</b>	Furnish and Install Water Service Pipe and Fittings on Residential Private Property (Rear Water Service Relocation) (See Sheet G-4 for add. Details) (Connection to House Valve)	78	EA		
<b>38</b>	Furnish and Install Water Service Pipe and Fittings on Residential Private Property (Rear Water Service Relocation) (See Sheet G-4 for add. Details) (Connection to Existing Meter)	27	EA		
<b>39</b>	Furnish and Install Water Service Pipe and Fittings on Residential Private Property (Rear Water Service Relocation) (Old Floresta Historic District Limits per Sheet G-4) (Connection to House Valve)	75	EA		
<b>40</b>	Furnish and Install Water Service Pipe and Fittings on Residential Private Property (Rear Water Service Relocation) (Old Floresta Historic District Limits per Sheet G-4) (Connection to Existing Meter)	25	EA		
<b>41</b>	Furnish and Install Water Service Pipe and Fittings on Residential Property (Connections to Existing Front Service)	366	EA		

42	Furnish and Install 1" RPZ Assembly	24	EA		
43	Furnish and Install 1.5" RPZ Assembly	24	EA		
<b>Water and Sewer (Cont.)</b>					
44	Furnish and Install 1" PVB Assembly	17	EA		
45	Furnish and Install 1.5" PVB Assembly	34	EA		
46	Furnish and Install 1" AVB Assembly	28	EA		
47	Furnish and Install 1.25" AVB Assembly	28	EA		
48	Furnish and Install 1.5" AVB Assembly	28	EA		
49	Testing of Pressure Vacuum Breaker Assembly	99	EA		
50	Furnish and Install 4" Gate Valve w/Box	1	EA		
51	Furnish and Install 6" Gate Valve w/Box	97	EA		
52	Furnish and Install 8" Gate Valve w/Box	16	EA		
53	Furnish and Install 10" Gate Valve w/Box	4	EA		
54	Furnish and Install 16" Butterfly Valve w/Box	2	EA		
55	Furnish and Install 20" Butterfly Valve w/Box	2	EA		
56	Furnish and Install 6" Plug Valve w/Box	3	EA		
57	Furnish and Install 8" Plug Valve w/Box	2	EA		
58	Furnish and Install 10" Plug Valve w/Box	1	EA		
59	Furnish and Install 14" Plug Valve w/Box	2	EA		
60	Furnish and Install 24" Plug Valve w/Box	3	EA		
61	Furnish and Install Fire Hydrant Assembly and 6" Gate Valve	35	EA		
62	Furnish and Install 6" X 6" Tapping Sleeve and Valve	2	EA		
63	Furnish and Install 8" X 8" Tapping Sleeve and Valve	3	EA		
64	Furnish and Install 10" X 8" Tapping Sleeve and Valve	1	EA		
65	Furnish and Install 10" X 10" Tapping Sleeve and Valve	1	EA		
66	Furnish and Install 24" X 8" Tapping Sleeve and Valve	2	EA		
67	Furnish and Install 20" X 6" Tapping Sleeve and Valve - PCCP	1	EA		
68	Furnish & Install 4" Line Stop	1	EA		

69	Furnish & Install 6" Line Stop	6	EA		
70	Furnish & Install 8" Line Stop	5	EA		
<b>Water and Sewer (Cont.)</b>					
71	Furnish and Install 10" Line Stop	1	EA		
72	Furnish and Install 20" PCCP Line Stop	1	EA		
73	Furnish and Install 24" Line Stop	5	EA		
74	Furnish and Install 14" x 12" Double Line Stop Bypass Assembly	1	LS		
75	Flowable Fill	100	CY		
76	Furnish and Install Sample Points	56	EA		
77	Chlorinating/Testing	34,190	LF		
78	Furnish and Install Fill & Flush Assembly	14	EA		
79	Furnish and Install ARV Manhole and ARV Assembly	11	EA		
80	Furnish and Install Doghouse WM Combo Air Valve Manhole and Air Valve Assembly	3	EA		
81	Furnish and Install Offset WM Combo Air Valve Manhole and Air Valve Assembly	3	EA		
82	Remove and Dispose of Existing Cast-Iron / PVC Water Main (Up to 12")	280	LF		
83	Remove and Dispose of Existing Asbestos-Cement Water Main (Up to 12")	325	LF		
84	Remove and Dispose of Existing Cast-Iron / PVC Force Main (Up to 16")	40	LF		
85	Abandon, Cut, Cap, and Grout Fill Existing 3" Water Main	7,885	LF		
86	Abandon, Cut, Cap, and Grout Fill Existing 4" Water Main	15,225	LF		
87	Abandon, Cut, Cap, and Grout Fill Existing 6" Water Main	16,015	LF		
88	Abandon, Cut, Cap, and Grout Fill Existing 8" Water Main	700	LF		
89	Abandon, Cut, Cap, and Grout Fill Existing 10" Water Main	1,480	LF		
90	Abandon, Cut, Cap, and Grout Fill Existing 12" Water Main	115	LF		
91	Abandon, Cut, Cap, and Grout Fill Existing 16" Water Main	65	LF		
92	Abandon, Cut, Cap, and Grout Fill Existing 20" Water Main	80	LF		
93	Abandon, Cut, Cap, and Grout Fill Existing 6" Force Main	1,130	LF		

94	Abandon, Cut, Cap, and Grout Fill Existing 8" Force Main	1,510	LF		
95	Abandon, Cut, Cap, and Grout Fill Existing 14" Force Main	75	LF		
<b>Water and Sewer (Cont.)</b>					
96	Abandon, Cut, Cap, and Grout Fill Existing 16" Force Main	3,840	LF		
97	Adjust Existing Manhole Rim to Finished Grade	10	EA		
98	Adjust Existing Valve Box to Finished Grade	10	EA		
99	Ductile Iron Fittings (Water Main) – Allowance (for Item 21)	1	ALLOWANCE		
100	Ductile Iron Fittings (Force Main) – Allowance (for Item 22)	1	ALLOWANCE		
101	Tie-in for 20" PCCP and 24-inch CIP Water Main	1	LS		
102	Tie-ins for Permanent Force Main Connections	1	LS		
103	Lift Station No. 53 Improvements	1	LS		
104	Lift Station No. 27 Improvements	1	LS		
<b>Sidewalk</b>					
105	Clearing & Grubbing	1.06	AC		
106	Removal of Existing Concrete	748	SY		
107	Replace/Relocate Single Mailbox	22	EA		
108	Tree Removal	31	EA		
109	Relocate Trees and Palms, Palm, >= 14' of Clear Trunk	19	EA		
110	Furnish and Install New Concrete Sidewalk (Min. 4" Thick)	150	SY		
111	Furnish and Install New Concrete Sidewalk and Driveways (Min. 6" Thick)	2550	SY		
112	Furnish & Install Truncated Domes per FDOT Index 304 (Detectable Warning)	340	SF		
113	Furnish and Install Pipe Handrail - Guiderail, Aluminum	22	LF		
<b>Stormwater</b>					
114	Furnish and Install Pipe Culvert – Round – 15" S/CD	60	LF		
115	Furnish and Install Pipe Culvert – Round – 18" S/CD	120	LF		
116	Furnish and Install Pipe Culvert – Round – 24" S/CD	220	LF		
117	Furnish and Install Pipe Culvert – Elliptical – 12" S/CD	230	LF		

<b>118</b>	Furnish and Install STRT Conc. Endwall (24", Single, 0-Degrees, Round)	1	EA		
<b>119</b>	Furnish and Install 15" Trench Drain	700	LF		
<b>Stormwater (Cont.)</b>					
<b>120</b>	Furnish and Install 15" French Drain	40	LF		
<b>121</b>	Furnish and Install 18" French Drain	1600	LF		
<b>122</b>	Furnish and Install Manhole (P-7) (<10' Deep)	3	EA		
<b>123</b>	Furnish and Install Ditch Bottom Inlet (Type C)	25	EA		
<b>124</b>	Furnish and Install Concrete Drop Curb	1,430	LF		
<b>125</b>	Clear and Grade Swale (including furnish and installation of new sod)	200	SY		
<b>126</b>	Enhanced Clear and Grade Swale (including furnish and installation of new sod)	200	SY		
<b>127</b>	Clear and Grade Swale Allowance (for Items 125 & 126)	1	ALLOWANCE		
<b>Roadway</b>					
<b>128</b>	Mill Existing Roadway Asphalt - City R-O-W (Average 1" Depth)	85,235	SY		
<b>129</b>	Furnish and Place Asphalt Overlay - City R-O-W (Average 1" Depth)	85,235	SY		
<b>130</b>	Furnish and Install Temporary Striping (Paint)	1	LS		
<b>131</b>	Furnish and Install Raised Pavement Markers (RPMs)	260	EA		
<b>132</b>	Furnish and Install 6" Solid Yellow Thermoplastic Striping	3.78	GM		
<b>133</b>	Furnish and Install 6" Solid White Thermoplastic Striping	12.97	GM		
<b>134</b>	Furnish and Install 24" Solid White Thermoplastic Striping	714	LF		
<b>135</b>	Furnish and Install Thermoplastic Speed Hump Marking	12	EA		
<b>136</b>	Furnish and Install Thermoplastic Message or Symbol, Standard, White	20	EA		
<b>137</b>	Relocate Single Post Sign	5	AS		
<b>Misc.</b>					
<b>138</b>	Fire Hydrant Flow Testing	35	EA		

**GRAND TOTAL BASE BID (SUM OF ITEMS 1 THROUGH 138)**

**\$ \_\_\_\_\_**

Name of Proposer: \_\_\_\_\_