

ATTACHMENT C – BID PRICE SHEET

ALL PRICES SHALL REMAIN VALID FOR ONE HUNDRED AND TWENTY (120) DAYS AFTER PROPOSAL OPENING.

SOLICITATION NO.: 26-019 35th Street CBDG Project

Prices shall contain all costs to include labor, equipment, tools, transportation, overhead, general and administrative, incidental expenses, operating margin and sub consultant costs (if any).

The price(s) will apply to the annual contract period. The price(s) provided must be stated specifically in dollars and cents, NOT a percentage increase. If a "0" (zero) is entered, that will be the fee the Proposer will receive if awarded this agreement. If a space is left blank, or a space is marked N/A, or the Department's Attachment "C", Bid Price Sheet is not utilized by the Bidder, the bid may be considered non-responsive.

The quantities are estimated for calculation purposes only and are not necessarily a representation of the actual quantities that will be authorized under this Agreement.

- **Do Not Re-Create, Modify or Replace the Department's Attachment "C" – Bid Price Sheet with your own version**
- **Do Not Change the Department's Estimated Quantity**
- **Do Not Change the Unit Type**
- **The Proposer MUST PROVIDE PRICING ON ALL ITEMS listed**

ACKNOWLEDGEMENT: I certify that I have read and agree to abide by all terms and conditions of this solicitation and that I am authorized to sign for the Bidder. I certify that the Bid submitted is made in conformance with all requirements of the solicitation. In submitting a response, the Bidder acknowledges they have read and agree to the solicitation terms and conditions and their submission is made in conformance with those terms and conditions.

Proposer Company Name: _____

FEID #: _____

Address: _____

Authorized Signature: _____ Date: _____

Printed Name: _____ Title: _____

Phone: _____ E-mail: _____



**CITY OF RIVIERA BEACH
BID SCHEDULE**

BASE BID: W 35TH STREET INFRASTRUCTURE IMPROVEMENTS					
BID ITEM NO.	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	EXTENDED PRICE
CONSTRUCTION - GENERAL					
1	BONDS AND INSURANCE (5%)	LS	1	\$	\$
2	MOBILIZATION (10%)	LS	1	\$	\$
3	MAINTENANCE OF TRAFFIC (5%)	LS	1	\$	\$
4	PERMIT FEES (1%)	AL	1	\$ 9,743.00	\$ 9,743.00
5	PROFESSIONAL AUDIO/VISUAL OF CONSTRUCTION SITE	LS	1	\$	\$
6	SURVEY AND RECORD DRAWINGS (LAYOUT/AS BUILTS)	LS	1	\$	\$
6A	OWNERS CONTINGENCY	AL	1	\$ \$ 25,000.00	\$ \$ 25,000.00
GENERAL SUBTOTAL					\$
DEMOLITION					
7	REMOVE EXISTING SIDEWALK (4")	SY	845	\$	\$
8	REMOVE EXISTING DRIVEWAY APRON (6") (CONCRETE)	SY	468	\$	\$
9	REMOVE EXISTING DRIVEWAY APRON (ASPHALT)	SY	256	\$	\$
10	REMOVE EXISTING DRIVEWAY - PRIVATE PROPERTY CONTINGENCY (6")	SY	50	\$	\$
11	REMOVE AND DISPOSE EXISTING ASPHALT PAVEMENT	SY	3,070	\$	\$
12	REMOVE EXISTING LIMEROCK BASE MATERIAL	SY	3,070	\$	\$
13	STABILIZATION OF SUBGRADE	SY	3,070	\$	\$
14	GROUT AND ABANDON EXISTING 4" ACP WATER MAIN	LF	920	\$	\$
15	GROUT AND ABANDON EXISTING 6" ACP WATER MAIN	LF	400	\$	\$
DEMOLITION SUBTOTAL					\$
ROAD WORKS AND SIDEWALK					
16	FURNISH AND INSTALL LIMEROCK BASE	SY	3,070	\$	\$
17	FURNISH AND PLACE ASPHALTIC CONCRETE PAVEMENT	SY	3,070	\$	\$
18	CONSTRUCT CONCRETE SIDEWALK (4")	SY	1,114	\$	\$
19	CONSTRUCT CONCRETE DRIVEWAY APRON AND SIDEWALK (6")	SY	468	\$	\$
20	CONSTRUCT DRIVEWAY - PRIVATE PROPERTY CONTINGENCY (6")	SY	50	\$	\$
21	CONSTRUCT VALLEY GUTTER	LF	2,425	\$	\$
22	MILL AND RESURFACE EXISTING ASPHALT (1-INCH)	SY	118	\$	\$
ROAD WORKS AND SIDEWALK SUBTOTAL					\$
MISCELLANEOUS					
23	REPLACE EXISTING SOD	SY	790	\$	\$
24	ADJUST RESIDENT GATES AT DRIVEWAY	EA	3	\$	\$
25	INSTALL PROJECT IDENTIFICATION SIGN	EA	2	\$	\$
26	REMOVE AND RELOCATE EXISTING MAILBOXES	EA	10	\$	\$
27	TREE REMOVAL AND INSTALLATION	LS	1	\$	\$
28	EXISTING UTILITY POLE RELOCATION	EA	2	\$	\$
29	EXISTING IRRIGATION SYSTEM RESTORATION	LS	1	\$	\$
MISCELLANEOUS SUBTOTAL					\$
STORM DRAINAGE					
30	FURNISH AND INSTALL TYPE C CURB INLET AND GRATE	EA	6	\$	\$
31	FURNISH AND INSTALL 48" DIAMETER ROUND MANHOLE	EA	3	\$	\$
32	FURNISH AND INSTALL INLET POLLUTION RETARDANT BAFFLES/WEIR	EA	2	\$	\$
33	FURNISH AND INSTALL 18" RCP STORM DRAIN	EA	470	\$	\$
34	FURNISH AND INSTALL SLOTTED 18" RCP STORM DRAIN W/ EXFILTRATION TRENCH	EA	850	\$	\$
35	CORE AND CONNECT INTO EXISTING DRAINAGE STRUCTURE	EA	2	\$	\$
STORM DRAINAGE SUBTOTAL					\$
SANITARY SEWER					
36	FURNISH AND INSTALL 8" CIP SEWER LINING	LF	969	\$	\$
37	CONTINGENCY/ALLOWANCE FOR 8" PVC SEWER REPAIRS	LF	60	\$	\$
38	GRAVITY SANITARY SEWER MANHOLE REHABILITATION	EA	3	\$	\$
39	FURNISH AND INSTALL SEWER LATERAL ADJUSTMENT/REPAIR	EA	18	\$	\$
40	FURNISH AND INSTALL CLEANOUT	EA	29	\$	\$
41	SANITARY MANHOLE RIM ADJUSTMENT	EA	6	\$	\$
SANITARY SEWER SUBTOTAL					\$
WATER MAIN					
42	FURNISH & INSTALL 6" PVC WATER MAIN PIPE VIA OPEN CUT	LF	1,340	\$	\$
43	FURNISH & INSTALL 1" PE WATER SERVICE WITH METER BOX (SINGLE)	EA	18	\$	\$
44	FURNISH & INSTALL 1.5" PE WATER SERVICE WITH METER BOX (DOUBLE)	EA	2	\$	\$
45	FURNISH & INSTALL 1" PE WATER SERVICE IN 2" PVC CASING WITH METER BOX (SINGLE)	EA	5	\$	\$
46	FURNISH & INSTALL 1.5" PE WATER SERVICE IN 4" PVC CASING WITH METER BOX (DOUBLE)	EA	1	\$	\$
47	FURNISH & INSTALL DIP PRESSURE MAIN FITTINGS	TN	2	\$	\$
48	FURNISH & INSTALL 6" GATE VALVE	EA	5	\$	\$
49	REMOVE AND DISPOSE EXISTING FIRE HYDRANT	EA	1	\$	\$
50	FURNISH & INSTALL FIRE HYDRANT ASSEMBLY	EA	4	\$	\$



CITY OF RIVIERA BEACH
BID SCHEDULE

BASE BID: W 35TH STREET INFRASTRUCTURE IMPROVEMENTS					
BID ITEM NO.	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	EXTENDED PRICE

WATER MAIN

51	CONNECTION TO EXISTING WATER MAIN	EA	3	\$	\$
52	FURNISH AND INSTALL 6" LINE STOP	EA	2	\$	\$
53	FURNISH AND INSTALL SAMPLE POINTS	EA	3	\$	\$
WATER MAIN SUBTOTAL					\$

PROPOSED PAVEMENT MARKING

54	6" SINGLE YELLOW THERMO	LF	550	\$	\$
55	12" SINGLE WHITE THERMO	LF	170	\$	\$
56	24" SINGLE WHITE THERMO	LF	30	\$	\$
PAVEMENT MARKING SUBTOTAL					\$

CONSTRUCTION SUBTOTAL (BASE BID)

\$

BID ALTERNATE 1: W 35TH STREET INFRASTRUCTURE IMPROVEMENTS					
BID ITEM NO.	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	EXTENDED PRICE

ROAD WORKS AND SIDEWALK

A-1	FURNISH AND INSTALL 6" CONCRETE PAVEMENT	SY	3,070	\$	\$
A-2	FURNISH AND INSTALL 6" LIMEROCK BASE	SY	3,070	\$	\$
A-3	DEDUCT: FURNISH AND INSTALL 8" LIMEROCK BASE	SY	3,070	\$	\$
A-4	DEDUCT: FURNISH AND PLACE ASPHALTIC CONCRETE PAVEMENT	SY	3,070	\$	\$
ROAD WORKS AND SIDEWALK SUBTOTAL					\$

CONSTRUCTION SUBTOTAL (BID ALTERNATE 1)

\$

TOTAL BID COST - BASE BID

\$ \$

TOTAL BID COST - BID ALTERNATE 1

\$ \$

TOTAL BID COST - BASE BID PLUS BID ALTERNATE 1

\$ \$