PROPOSAL FORM

_____
(COMPANY NAME)

_____
(COMPANY ADDRESS)

_____
(COMPANY CITY & STATE)

_____
(COMPANY ZIP CODE)

CONTACT NAME _____

PHONE NUMBER _____

FACSIMILE NUMBER _____

EMAIL ADDRESS _____

_____ _____
FEDERAL TAX I.D. # DATE SUBMITTED

FOR THE CONSTRUCTION OF: **LYONS ROAD NORTH OF LAKE WORTH DRAINAGE DISTRICT (LWDD) L-30 CANAL TO BOYNTON BEACH BOULEVARD & LYONS ROAD AND BOYNTON BEACH BOULEVARD INTERSECTION IMPROVEMENTS PALM BEACH COUNTY PROJECT NO. 2018503 & 2020110**

TO THE BOARD OF COUNTY COMMISSIONERS OF
PALM BEACH COUNTY, FLORIDA:

We, the undersigned (Contractor), hereby declare that no person or persons, firm or corporation, other than the undersigned, are interested in this Proposal as principals, and that this Proposal is made without collusion with any person, firm, or corporation, and that we are not on the Scrutinized Companies List as stated on page SC-1, and we have carefully and to our full satisfaction examined the Contract Documents, and that we have made a full examination of the location of the proposed Work and the source of supply of Materials, and we hereby agree to furnish and pay for all necessary labor, Equipment, Materials and services, fully understanding that the quantities shown herein are approximate only and that we will fully complete all Work in accordance with the Contract Documents and the requirements under them of the Engineer, within the time limit specified in this Proposal for the following unit prices, to wit:

BID PROPOSAL
LYONS ROAD FROM LWDD L-30 CANAL TO BOYNTON BEACH BOULEVARD and
LYONS ROAD AND BOYNTON BEACH BOULEVARD INTERSECTION IMPROVEMENTS
CONTRACT
PBC PROJECT # 2018503 & 2020110

#	FDOT ITEM NUMBER	ITEM DESCRIPTION	QTY	UNITS	UNIT PRICE	AMOUNT
ROADWAY ITEMS						
1	0101 1	Mobilization	1	LS		$ -
2	0102 1	Maintenance of Traffic (Including Ped. MOT)	1	LS		$ -
3	0110 1 1	Clearing and Grubbing	1	LS		$ -
4	104 11	Floating Turbidity Barrier	1,200	LF		$ -
5	0104 18	Inlet Protection System	84	EA		$ -
6	0120 1	Regular Excavation	22,865	CY		$ -
7	0120 6	Embankment (Compacted In Place)	2,062	CY		$ -
8	N/A	Canal Excavation	287	CY		$ -
9	N/A	Canal Embankment(Compacted In Place)	359	CY		$ -
10	0285 713	Optional Base, Base Group 13	38,274	SY		$ -
11	0285 713	Optional Base, Base Group 2	55	SY		$ -
12	0327 70 1	Mill Existing Asphalt Pavement, 1" Avg Depth	114,091	SY		$ -
13	0334 1 13	Superpave Asphalt Concrete (Traffic C)(1.5")	4,970.18	TN		$ -
14	0337 7 82	Asphalt Concrete Friction Course (1.0") (FC-9.5)	8,719.88	TN		$ -
15	0339 1	Miscellaneous Asphalt Pavement	101.7	TN		$ -
16	0400 4 1	Concrete Class IV, Culverts	78.4	CY		$ -
17	0415 1 1	Reinforcing Steel-Roadway	15,390	LB		$ -
18	0425 1311	Inlets (Curb) (Type P-1)	0	EA		$ -
19	0425 1341	Inlets (Curb) (Type P-4) (<10')	0	EA		$ -
20	0425 1351	Inlets (Curb) '(Type P-5) (<10')	8	EA		$ -
21	0425 1355	Inlets (Curb) (Type P-5) (Partial)	12	EA		$ -
22	0425 1361	Inlets (Curb) (Type P-6) (<10')	3	EA		$ -
23	0425 1365	Inlets (Curb) (Type P-6) (Partial)	19	EA		$ -
24	0425 1441	Inlets (Curb) (Type J-4) (<10')	1	EA		$ -
25	0425 1525	Inlets (Ditch Bottom) (Type C) (Partial)	1	EA		$ -
26	0425 1545	Inlets (Ditch Bottom) (Type D) (Partial)	3	EA		$ -
27	0425 2 41	Manholes (Type P-7) (10')	1	EA		$ -
28	0425 2 43	Manhole Type P-7 (Partial)	7	EA		$ -
29	0425 4	Adjust Inlets	3	EA		$ -
30	425 5	Adjust Drainage Manhole	4	EA		$ -
31	N/A	Yard Drain	19	EA		$ -
32	0430 17 4118	18" Pipe Culvert, Round	10	LF		$ -
33	0430 17 5112	Pipe Culvert (12")	112	LF		$ -
34	0430 17 5118	Pipe Culvert (18" S/CD)	102	LF		$ -
35	N/A	Storm Sewer Pumping (Exist.) (24" or Less) (See Sp's)	8,259	LF		$ -
36	N/A	Storm Sewer Pumping (Exist.) (>24" to 48") (See Sp's)	7,292	LF		$ -
37	0443 70 3	French Drain, 18" Pipe	370	LF		$ -
38	0520 1 10	Concrete Curb & Gutter (Type F)	42,812	LF		$ -
39	N/A	Engraving of Curb Face (See Sp's)	8	EA		$ -
40	N/A	Color Treated Stamped Concrete	923	SY		$ -
41	0522 1	Concrete Sidewalk (4" Thick)	1,046	SY		$ -
42	0522 2	Concrete Sidewalk & Driveway (6" Thick)	581	SY		$ -
43	0570 1 2	Sodding	40,782	SY		$ -
44	0530 3 3	Riprap, Rubble, Bank and Shore	142	TN		$ -
45	0536 1 1	Guardrail - Roadway	4,100	LF		$ -
46	0536-6	Pipe Rail for Guardrail	1,300	LF		$ -
47	0536 85 20	Guardrail End Treatment-Trailling Anchorage	2	EA		$ -

BID PROPOSAL
LYONS ROAD FROM LWDD L-30 CANAL TO BOYNTON BEACH BOULEVARD and
LYONS ROAD AND BOYNTON BEACH BOULEVARD INTERSECTION IMPROVEMENTS
CONTRACT
PBC PROJECT # 2018503 & 2020110

#	FDOT ITEM NUMBER	ITEM DESCRIPTION	QTY	UNITS	UNIT PRICE	AMOUNT
48	0536 85 24	Guardrail End Treatment-Parralel Approach Terminal	2	EA		$ -
49	0630 2 11 2A	2 - 2" PVC Conduits (Sch 40) (Open Trench)	10,019	LF		$ -
50	0630 2 12 2 2	2 - 2" PVC Conduits (Sch 40) (Directional Bore)	1,555	LF		$ -
51	633-1-121	Fiber Optic Cable (F&I) (Underground) (2-12 FSM Fibres)	1,000	LF		$ -
52	0633 1122	Fiber Optic Cable (F&I) (Underground) (13-48 Fibers)	18,300	LF		$ -
53	633-2-31	Fiber Optic Connection (Install) (Splice)	5	EA		$ -
54	633-3-12	Fiber Optic Connection Hardware (F&I) (Splice Tray)	5	EA		$ -
55	0635-2-11	Pull Box (Small) (17" x 30" x 24"D)	17	EA		$ -
56	0635-2-15	Pull Box (Large) (30" x 48" x 24"D)	9	EA		$ -
57	0646-1-40	ALUMINUM SIGNALS POLE, RELOCATE	2	EA		$ -
58	0676 2300	ITS Cabinet (Hub) (Provide & Install)	1	EA		$ -
SUBTOTAL (ROADWAY)						**$ -**
UTILITY ADJUSTMENT						
59	N/A	Construction Survey	1	LS		$ -
60	N/A	Furnish and Install 16" DIP Water Main (Restrained)	423	LF		$ -
61	N/A	Furnish and Install 16" DIP Megalug Mechanical Joint Restraint	83	EA		$ -
62	N/A	Furnish and Install Ductile Iron Fittings for Water Main	8.26	TN		$ -
63	N/A	Removal and Disposal of Existing 16" DIP Water Main	1	LS		$ -
64	N/A	16" Diameter Connection to Exist WM include Restraining Exist WM	22	EA		$ -
65	N/A	16" Existing Pipe Bell Joint Restraint Harness	22	EA		$ -
66	N/A	Sample Point	22	EA		$ -
67	N/A	Adjustment of Air Release Valve Manhole	8	EA		$ -
68	N/A	Valve Box Replacement and Adjustment	88	EA		$ -
69	N/A	Record Drawings	1	LS		$ -
70	N/A	Preconstruction Video Taping	1	LS		$ -
71	N/A	Density Tests	66	EA		$ -
72	N/A	Proctor Tests	22	EA		$ -
SUBTOTAL (UTILITIES)						$ -
CONTINGENCY ITEMS						
56	0102 14	Traffic Control Officer (Non MOT)	60	HR		$ -
57	0102 99	Changeable (Variable Message) Sign (Non MOT)	11	ED		$ -
58	0121 70	Flowable Fill	72	CY		$ -
59	N/A	Storm Sewer Cleaning(Exist.) (24" or Less)(See Sp's)	8,269	LF		$ -
60	N/A	Storm Sewer Cleaning(Exist.) (>24" to 48")(See Sp's)	7,292	LF		$ -
61	N/A	Box Culvert Cleaning (Exist.) (10' x 6')	98	LF		$ -
62	N/A	Support Existing Utilities During Proposed Utilities/Drainage Installation	700	LF		$ -
63	N/A	Single Line Stop (16")	11	EA		$ -
64	N/A	Relocation or Adjustment of Existing Fire Hydrant	19	EA		$ -
SUBTOTAL (CONTINGENCY)						**$ -**
SIGNALIZATION ITEMS						

BID PROPOSAL
LYONS ROAD FROM LWDD L-30 CANAL TO BOYNTON BEACH BOULEVARD and
LYONS ROAD AND BOYNTON BEACH BOULEVARD INTERSECTION IMPROVEMENTS
CONTRACT
PBC PROJECT # 2018503 & 2020110

#	FDOT ITEM NUMBER	ITEM DESCRIPTION	QTY	UNITS	UNIT PRICE	AMOUNT
63	630-2-11-2A	Additional 2" PVC (Sch 40) Conduit (In Open Trench)	175	LF		$ -
64	630-2-12-2-2	2-2" (HDPE SDR 11) Under Pavement Conduit (Directional Bore)	234	LF		
64	630-2-12-2-4	4-2" (HDPE SDR 11) Under Pavement Conduit (Directional Bore)	400	LF		$ -
65	630-2-12-2-7	7-2" (HDPE SDR 11) UNDER PAVEMENT CONDUIT (DIRECTIONAL BORE)	305	LF		$ -
66	630-2-14-1	1" RIGID CONDUIT HOT DIPPED GALVANIZED CONDUIT SURFACE MOUNTED	120	LF		$ -
67	632-7-1-7	SIGNAL CABLE- 7 CONDUCTOR	1	PI		$ -
68	632-7-1-7A	PEDESTRIAN SIGNAL CABLE- 7 CONDUCTOR	1	PI		$ -
69	632-7-1-19	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	1	PI		$ -
70	632-7-4	Signal Cable (Adjust)	1	PI		$ -
71	632-7-6	Signal Cable, Remove - In Intersection, adjust	2	PI		$ -
72	635-2-12-A	Pull Box (17" x 30" x 12"D) Heavy Duty Covers (Tier 22)	27	EA		$ -
73	639-1-121	Electrical Power Service (F&I) (Underground) Meter Furnished By Power Company	2	AS		$ -
74	639-2-1-3	ELECTRICAL SERVICE WIRE (SIGLE PHASE 3-WIRE, TRIPLEX)	120	LF		$ -
75	639-3-11	Electrical Service Disconnect (F&I) Pole Mount	1	EA		$ -
76	641-1-12-16	Prestressed Concrete Pole, F&I, 16' Type P-II Service Pole	2	EA		$ -
77	641-2-80	Concrete Pole Removal - Deep (Includes Pole And Complete Removal of the Pole Foundation Depth of Up To 25 Feet) Includes Disposal of Pole When Instructed by Engineer	3	EA		$ -
78	646-1-11	Aluminum Signals Pole, Pedestal	3	EA		$ -
79	646-1-12	ALUMINUM SIGNALS POLE, FURNISH & INSTALL PEDESTRIAN DETECTOR POST	4	EA		$ -
80	646-1-60	Aluminum Signals Pole, Remove	7	EA		$ -
81	649-22-1L	Mast Arm Assembly with Street Light, Furnish and Install On Existing Foundation, Single Arm 30' (A30/S-P1/S/L)	1	EA		$ -
82	649-22-6	MAST ARM ASSEMBLY , FURNISH AND INSTALL ON EXISTING FOUNDATION, SINGLE ARM 50' (A50/S-P3/S)	1	EA		$ -
83	649-22-6L	Mast Arm Assembly with Street Light, Furnish and Install On Existing Foundation, Single Arm 50' (A50/S-P3/S/L)	1	EA		$ -
84	649-22-21-HD	MAST ARM ASSEMBLY , FURNISH AND INSTALL ON EXISTING FOUNDATION, SINGLE ARM 78' HEAVY DUTY(A78/S-P6/S-HD)	1	EA		$ -
85	649-22-21L-HD	Mast Arm Assembly with Street Light, Furnish and Install On Existing Foundation, Single Arm 78' Heavy Duty (A78/S-P6/S/L-HD)	1	EA		$ -

BID PROPOSAL
LYONS ROAD FROM LWDD L-30 CANAL TO BOYNTON BEACH BOULEVARD and
LYONS ROAD AND BOYNTON BEACH BOULEVARD INTERSECTION IMPROVEMENTS
CONTRACT
PBC PROJECT # 2018503 & 2020110

#	FDOT ITEM NUMBER	ITEM DESCRIPTION	QTY	UNITS	UNIT PRICE	AMOUNT
86	649-2-12-40	Drilled Shaft Foundation Assembly, 12' Deep and 4.0' Diameter, Furnish and Install (Ds/12/4.0)	1	EA		$ -
87	649-2-12-45	Drilled Shaft Foundation Assembly, 12' Deep and 4.5' Diameter, Furnish and Install (Ds/12/4.5)	1	EA		$ -
88	649-2-16-45	Drilled Shaft Foundation Assembly, 16' Deep and 4.5' Diameter, Furnish and Install (DS/16/4.5)	1	EA		$ -
89	649-2-18-45	Drilled Shaft Foundation Assembly, 18' Deep and 4.5' Diameter, Furnish and Install (DS/18/4.5)	1	EA		$ -
90	649-2-20-50	Drilled Shaft Foundation Assembly, 20' Deep and 5.0' Diameter, Furnish and Install (DS/20/5.0)	2	EA		$ -
91	649-2-20-50-AD	Additional Depth for Drilled Shaft Foundation Assembly, 20' Deep and 5.0' Diameter, Furnish and Install (DS/20/5.0)	12	LF		$ -
92	649-26-05	STEEL MAST ARM ASSEMBLY , REMOVE, DEEP FOUNDATION - BOLT ON ATTACHMENT	2	EA		$ -
93	650-1-13	Vehicular Traffic Signal, Furnish & Install, Aluminum, 3 Section, 1 Way	11	AS		$ -
94	650-1-14	Vehicular Traffic Signal, Furnish & Install Aluminum, 4 Section, 1 Way	2	AS		$ -
95	650-1-15	Vehicular Traffic Signal, Furnish & Install Aluminum, 5 Section, 1 Way	1	AS		$ -
96	650-1-60	TRAFFIC SIGNAL HEAD ASSEMBLY, REMOVAL	5	EA		$ -
97	653-191	Pedestrian Signal - Count Down (1-Way) Aluminum	6	EA		$ -
98	653-192	Pedestrian Signal - Count Down (2-Way) Aluminum	3	EA		$ -
99	653-1-60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL	4	EA		$ -
99	660-1-109	Loop Detector Inductive, F&I, Type 9	42	EA		$ -
100	660-2-106-B	Loop Assembly (Type F - 46')	42	EA		$ -
101	660-4-60	VEHICLE DETECTION SYSTEM - VIDEO, REMOVE	8	EA		$ -
101	665-1-11	Pedestrian Detector, Furnish & Install, Standard	8	EA		$ -
102	690-80	Remove Span Wire Assembly	1	PI		$ -
103	700-5-21	INTERNALLY ILLUMINATED SIGN (6'), LED	1	EA		
104	700-5-22	Internally Illuminated Sign (8') Fluorescent	3	EA		$ -
105	715-11-211-L1	Furnish And Install 168 Watt Cobra Head LED Luminaire	1	EA		$ -
106	715-680000	Light Pole Relocate	1	EA		$ -
107	715-11-211-L2	Furnish And Install 263 Watt Cobra Head LED Luminaire	3	EA		$ -
SUBTOTAL (SIGNALIZATION)						**$ -**
					TOTAL BID	**$ -**

THE COUNTY DOES NOT GUARANTEE THE ACCURACY OF THE FORMULAS AND EXTENSIONS USED IN THIS SPREADSHEET.

THE ITEMS AND QUANTITIES ABOVE, SHALL GOVERN OVER THE PLANS.

PAY ITEM FOOTNOTES IN CONSTRUCTION PLANS SHALL ALSO BE INCLUDED IN ITEM UNIT PRICE.

Note #	FDOT Item #	PAY ITEM FOOTNOTES

BID PROPOSAL
LYONS ROAD FROM LWDD L-30 CANAL TO BOYNTON BEACH BOULEVARD and
LYONS ROAD AND BOYNTON BEACH BOULEVARD INTERSECTION IMPROVEMENTS
CONTRACT
PBC PROJECT # 2018503 & 2020110

#	FDOT ITEM NUMBER	ITEM DESCRIPTION	QTY	UNITS	UNIT PRICE	AMOUNT
1	All	All costs for Maintenance of Traffic (MOT) and mobilization shall be considered incidental to, and shall be included in, unit prices for the pay items.				
2	All	All items shall include cost to furnish and install unless otherwise noted.				
3	All	FDOT Item numbers are for reference only.				
4	0110 1 1	Removal of Median Trees & Small Plant Material shall be included in this item. Selective Removal.				

PROPOSAL FORM

PROJECT NO. 2018503 & 2020110

TOTAL BID
$ _____
IN FIGURES

The Contractor acknowledges that Addenda _____ thru _____ have been received and that related costs are reflected in the submitted bid. Contractor has committed to _____***% SBE participation*** as set forth on the Schedule 1 and Schedule 2 that are completed and submitted by Contractor. Contractor shall comply with said goal if awarded the Contract.

The Contractor hereby certifies and agrees that the following information is correct: In preparing its response to the Solicitation, the Contractor has considered all proposals submitted from qualified, potential Subcontractors and suppliers, and has not engaged in "discrimination" as defined in the County's Commercial Nondiscrimination Policy as set forth in Resolution R2025-0748 as amended, to wit: discrimination in the solicitation, selection or commercial treatment of any Subcontractor, vendor, supplier or commercial customer on the basis of race, color, national origin, religion, ancestry, sex, age, marital status, familial status, sexual orientation, disability, or genetic information, or on the basis of any otherwise unlawful use of characteristics regarding the vendor's, supplier's or commercial customer's employees or owners; provided that nothing in this policy shall be construed to prohibit or limit otherwise lawful efforts to remedy the effects of discrimination that have occurred or are occurring in the County's relevant marketplace of Palm Beach County. Without limiting the foregoing, "discrimination" also includes retaliating against any person or other entity for reporting any incident of "discrimination." Without limiting any other provision of the solicitation, it is understood and agreed that, if this certification is false, such false certification will constitute grounds for the County to reject the proposal submitted by the Contractor for this Solicitation, and to terminate any contract awarded based on the response. As part of its proposal, the Contractor shall provide to the County a list of all instances within the immediate past four (4) years where there has been a final adjudicated determination in a legal or administrative proceeding in the State of Florida that the Contractor discriminated against its Subcontractors, vendors, suppliers or commercial customers, and a description of the status or resolution of that complaint, including any remedial action taken. As a condition of submitting a proposal to the County, the Contractor agrees to comply with the County's Commercial Nondiscrimination Policy as described in Resolution R2025-0748, as amended.

The Contractor further agrees to perform all force account Work, as provided for in the General Provisions, and to execute the Contract and return to the County, along with a Contract Bond and Certificate of Insurance within fourteen (14) Working Days of the date of the Letter of Intent to

PROPOSAL FORM

Award and to commence Work with adequate forces and Equipment within fourteen (14) Calendar Days of the date set forth in the Notice to Proceed and to fully complete all contracted Work under the same in accordance with Contract Documents within the Contract Time.

THE TIMELY COMPLETION OF THIS PROJECT IS CRITICAL TO THE HEALTH, SAFETY AND WELFARE OF THE TRAVELING PUBLIC. It is the desire of Palm Beach County to expedite the construction and opening to traffic of the project. The Contractor shall be required to work such hours, weekends and/or Holidays to meet the required Contract schedules.

The Contractor shall complete in full all Work under this Contract within not more than eight hundred twenty day [820]*) Calendar Days (Contract Time). It is further agreed that should the Contractor fail to complete all Work under this Contract within the Contract Time; then, due to the criticalness of the timely completion of this project, liquidated damages for failure to meet these provisions shall be in accordance with Section 8 of the General Provisions.

The Contractor further agrees to furnish a sufficient and satisfactory Bond, on the form herein provided, in the sum of not less than 100% of the Contract price of the Work as indicated by the approximate quantities shown herein.

The Contractor further agrees to bear the full cost of maintaining all Work until the final acceptance, as provided in the Contract Documents.

Accompanying this Proposal is a Proposal Guaranty (Bid Bond) made payable to Palm Beach County, a Political Subdivision of the State of Florida, in the sum of 5% of amount Bid which is to be forfeited as liquidated damages if, in case this Proposal is accepted, the undersigned should fail to execute the attached Contract under the conditions of this Proposal. Otherwise, the Bid Bond is to be returned to the Contractor upon the delivery of a satisfactory Contract Bond.

Company Name: _____ Authorized Officer: _____
(Print)

Address: _____ Signature: _____

_____