

**BOARD OF COUNTY COMMISSIONERS
PALM BEACH COUNTY, FLORIDA
ENGINEERING AND PUBLIC WORKS
ROADWAY PRODUCTION DIVISION**

**Project Name: Lyons Road North of Lake Worth Drainage District (LWDD)
L-30 Canal to Boynton Beach Boulevard & Lyons Road and Boynton Beach
Boulevard Intersection Improvements**

Project Number: 2018503 & 2020110

Addendum No. 4

Date of Issuance: October 9, 2026

BID DUE DATE HAS BEEN CHANGED TO OCTOBER 27, 2026
--

SPECIFICATIONS

Delete	Insert	Add
A-C	A-D	
B-B	B-D	
C-B	C-D	
		SP-58D thru SP-60D
PER-1	PER-1D	
P-1C thru P-9C	P-1D thru P-9D	

It is required that **ADDENDUM NO. 4** be acknowledged in the space provided on the **PROPOSAL FORM**.

Approved By: Kathleen Farrell

Digitally signed by Kathleen Farrell
DN: DC=org, DC=ptbcgov, OU=Enterprise, OU=Users, CN=Kathleen Farrell, E=KFarrell@ptbc.gov
I have reviewed this document
Location: Kathleen O. Farrell, P.E., Roadway Production Division
Date: 2026.10.09 15:28:23-04'00'
Foxit PDF Editor Version: 12.1.0

INDEX

Bidding Forms

Cover Sheet.....	Cover
Index	A
Notice to Bidders	B
Advertisement for Bid.....	C
Submittals Requested with Bid	D
Instructions to Bidders	ITB-1 to ITB-12

Specifications / Provisions

Special Provisions.....	SP-1 to SP-32
Special Provisions [Project Specific].....	SP-33 to SP-41
Special Provisions [Requests for Information (Contractor RFI's)]	SP-42 to SP-60
Standard Specifications	SS-1
Technical Special Provisions	TSP-1 thru TSP-222
General Provisions	GP-1 to GP-120

Release / Permits / OSBD Forms

Driveway Construction Release.....	DE-1 to DE-2
Permits	PER-1 to PER-91
OSBD Forms.....	SBD-1 to SBD-7

Proposal

Proposal Form.....	P-1 to P-9
--------------------	------------

Bid Forms / Requirements / Bid Bond

Palm Beach County Local Preference Ordinance & Cert. of Business Location.....	LP-1 to LP-2
Scrutinized Companies	SC-1
Bid Bond	BB-1 to BB-2
Certificate of Resolution	CC-1

Contract Forms / Requirements / Construction Bond

Contract.....	C-1 to C-3
Public Construction Bond.....	PCB-1 to PCB-4
Certification of Sublet Work.....	SW-1
Certificate of Insurance.....	CI-1
Construction Coordination Forms.....	CONST-1 to CONST-11

NOTICE TO BIDDERS

NON-MANDATORY PRE-BID MEETING

Date: **Thursday September 3, 2026**

Time: **2:30 p.m.**

Location: **Engineering and Public Works Department
3rd Floor Main Conference Room (3W-12)
2300 North Jog Road
West Palm Beach, Florida, 33411-2745**

BID OPENING MEETING

Date: **Tuesday, October 27, 2026**

Time: **2:00 p.m.**

Location: **Engineering and Public Works Department
3rd Floor Conference Room (3W-12)
2300 North Jog Road
West Palm Beach, Florida, 33411-2745**

Webex Option for **both meetings**:

<https://pbc-gov.webex.com/meet/Eng-RoadwayBids>

If there are any questions concerning these meetings, please contact:

Roadway Production Division
(561) 684-4150

ADVERTISEMENT FOR BID

Sealed Bids will be received by the Board of County Commissioners, Palm Beach County, Florida, in the Office of Palm Beach County Engineering and Public Works Department, Roadway Production Division, located at 2300 North Jog Road, Third Floor Room 3W-33, West Palm Beach, Florida, 33411-2745, up to 2:00 P.M., local time, and opened in the 3rd Floor Conference Room (3W-12) on **Tuesday, October 27, 2026**, for furnishing all Materials, labor, Equipment and supplies necessary for the Construction of:

**Lyons Road North of Lake Worth Drainage District (LWDD) L-30 Canal to Boynton
Beach Boulevard & Lyons Road and Boynton Beach Boulevard Intersection
Improvements**

PALM BEACH COUNTY PROJECT NO. 2018503 & 2020110

All conditions and requirements for Bid submission, consideration, and award are contained in the Contract Documents, which are posted on the following Palm Beach County web site:

<https://pbcvssp.pbc.gov/vssprd/Advantage4>

To review the Contract Documents for this project, go to the above URL and click on the project hyperlink. Contractors may then download and print the Contract Documents (Plans, Specifications, Excel Proposal Forms, check list “with required forms” and any other related documents).

Hard copy documents will be available at the Department for a non-refundable service fee of **\$75**. The Contractor shall contact Palm Beach County Roadway Production Division at (561) 684-4150 in advance to arrange for hard copies.

All Bids shall be submitted in accordance with the Bid Documents, including but not limited to the General Provision Section 2 and accompanied by the documentation referenced therein.

The NON-MANDATORY Pre-Bid Meeting will be held on Thursday, September 3, 2026 at 2:30 P.M., in the Third Floor Main Conference Room (3W-12) in the Palm Beach County Building at 2300 North Jog Road, West Palm Beach, Florida. *Webex Option* – <https://pbc.gov.webex.com/meet/Eng-RoadwayBids>. Attendance at this pre-bid meeting is not mandatory but is highly recommended and strongly encouraged. To the extent you are unable to attend the pre-bid meeting, you may request and obtain an audio recording of the meeting by contacting Palm Beach County Roadway Production Division at (561) 684-4150.

The Board of County Commissioners reserves the right to reject any or all Bids. By order of the Board of County Commissioners, Palm Beach County, Florida.

ATTEST:
SHANNON RAMSEY-CHESSMAN, CLERK AD INTERIM
OF THE CIRCUIT COURT & COMPTROLLER

PALM BEACH COUNTY, a political
subdivision of the State of Florida, by and
through its Board of County Commissioners

DAVID RICKS, P.E., COUNTY ENGINEER

BY: Sara Baxter, Mayor

PUBLISH: PALM BEACH POST
SUNDAY: August 23, 2026
SUNDAY: August 30, 2026

PERMITS

The Contractor is advised that the following pages are copies of the applicable permits for this project. If a permit document includes copies of plan sheets, those pages may not be included herein, but are available from the Department upon request or from the permitting agency.

All general and special conditions required by specific permit(s) shall be executed accordingly and it is the Contractor's responsibility to ensure compliance with said conditions.

Any permits requiring "as-built" information and/or certification shall be prepared by a professional engineer or land surveyor licensed in the state of Florida and shall be the responsibility of the Contractor.

The Contractor is responsible for assuring the completion of appropriate construction certifications, and submittal of the construction completion certifications to permitting agencies as required by each permit referenced in these documents.

All costs associated with meeting said requirements, if not included in a bid item, shall be incidental to the Contract and no compensation, either monetary or time, shall be considered.

The Contractor agrees that the entirety of the permits listed below shall govern.

Contract Permits

Permit Number	Permitting Agency	Location of Full Permit Documents
50-111047-P	South Florida Water Management Dist.	https://my.sfwmd.gov/ePermitting/PopulateLOVs.do?flag=1
RW-24-0111	Lake Worth Drainage Dist.	Accela Citizen Access
RW-24-0112	Lake Worth Drainage Dist.	Accela Citizen Access
2026-A-496-00007	FDOT	https://osp.fdot.gov/#!/ProcessType/bcea6559-de4d-4d27-a8ba-015bfdc28336/Process
2025-C-496-00001	FDOT	https://osp.fdot.gov/#!/ProcessType/bcea6559-de4d-4d27-a8ba-015bfdc28336/Process

SPECIAL PROVISIONS

RESPONSE TO CONTRACTORS REQUESTS FOR INFORMATION

Date: September 28, 2026

Company Name: General Asphalt Co. LLC.

Person Name: Scot Paulitsch

QUESTION: The Index of Roadway Plans are missing the following elements:

C2 1 of 3 SFWMD STD Civil Details Vehicle Barrier

C2 3 of 3 Two Span Gate

GR-1 thru GR-6 Roadway Soil Survey

RESPONSE: Refer to addendum 4 for materials.

Date: October 05, 2026, 9:45 AM

Company Name: OHLA USA, Inc.

Person Name: Jared Moore

QUESTION: Can you please confirm weather SP-12.5 black base may be used in lieu of limerock matter for the OBG 13 line item

RESPONSE: See Sheet 13 in Addendum 4.

Date: October 05, 2026, 11:30 AM

Company Name: M & M Asphalt, dba All County Paving.

Person Name: Rudy Pollselli

QUESTION: You have added scope to the project will you be adding additional time for such work?

Is the bid date changing from the 13th Add # 3 does not address?

RESPONSE: Bid date will be addressed with this Addendum.

QUESTION: Where is the Guardrail Removal pay item?

RESPONSE: Guardrail removal is included in Clearing and Grubbing Pay Item.

Date: October 05, 2026, 12:08 PM

Company Name: Ranger Construction

Person Name: Andrew Maniotis

QUESTION: Bid Items 13 and 14—Quantity Clarification: Please confirm the quantities for Bid Items 13 and 14 in the revised bid tabulation. Even when combined, the quantities shown in the two plan sets (2018503 and 2020110) are less than the revised bid quantities. Additionally, the paving limits overlap between the two projects, so simply adding the quantities from both plan sets would double-count the overlapping areas. Please clarify how the revised quantities were calculated and confirm that overlapping paving areas are counted only once.

RESPONSE: No change to the Pay Items

SPECIAL PROVISIONS

QUESTION: L.W.D.D. L-28 Canal Box Culvert—Flow Maintenance Requirements: The plans and specifications do not identify whether bypass pumping is required, whether the canal may be temporarily blocked for the duration of the box culvert work, or whether an alternate means of maintaining flow must be provided. Our understanding is that Lake Worth Drainage District requires construction and maintenance plans to be submitted for review to ensure canal flow is not impeded. Has the County submitted the proposed work to the District, and has the District required a flow maintenance plan? Please clarify whether the Engineer of Record's design anticipates bypass pumping or temporary canal closure, and provide the applicable requirements, restrictions, and bid item under which any required flow maintenance work will be paid.

RESPONSE: See LWDD Permit for requirements by LWDD.

Date: October 05, 2026, 9:45 AM

Company Name: Rosso Development

Person Name: Josph Rosso III

QUESTION: Can a bid item be added for the forcemain deflections at station 265+80 to 267+50, LT shown on the utility plans? There is no item for forcemain work.

RESPONSE: See Pay Items in this addendum.

QUESTION: Most of these valve boxes called out to be replaced are in the active travel lanes. I just want to confirm you want new valve boxes and we can't plan to adjust them if necessary. These will be pretty expensive due to the MOT and compaction to dig the old ones out of the ground and install new ones.

RESPONSE: The Valve box adjustment Pay Item has been moved to the contingency.

Date: October 05, 2026, 9:37 AM

Company Name: Guaranteed Fence Corp

Person Name: Eduardo Hinestroza

QUESTION: I reviewed the addendum plans and noticed that the pipe rail quantity was added from approximately **1,300 LF and Guardrail increases from 1300 LF to 4100 LF on the pay item list**. However, I am unable to identify the plan revisions or details in the addendum drawings that account for this increase.

Could you please clarify where the additional pipe rail is shown in the revised plans or provide the basis for the updated quantity?

RESPONSE: Pay Items remain the same

Date: October 06, 2026, 1:49 PM

Company Name: Ranger Construction

Person Name: Andrew Maniotis

QUESTION: Guardrail Quantities: Per Project no. 2020110 on sheet 2 in the summary of quantities, 1,300 LF of guardrail is identified. Per addendum 3, 1,300 LF of pipe rail has been added for this same quantity of guardrail. Per Project No. 2018503 on sheet 2 in the summary of

SPECIAL PROVISIONS

quantities, no guardrail is called out as a Bid item. Where in project No. 2018503 is the remaining 2,800 LF of guardrail?

RESPONSE: Noted

QUESTION: Revised Addendum 3 Bid Items Worksheet: Can you please confirm the numbering system for the pay items worksheet.

RESPONSE: See new Pay item Sheet this addendum.

Date: October 07, 2026, 10:22 AM

Company Name: Johnson Davis

Person Name: Chris Johnson

QUESTION: Please tell us where to find the J-4 Inlet you as a bid item, I can't locate it in the revised plans you sent out?

RESPONSE: Item has been removed from the pay item sheet.

PROPOSAL FORM

(COMPANY NAME)

(COMPANY ADDRESS)

(COMPANY CITY & STATE)

(COMPANY ZIP CODE)

CONTACT NAME _____

PHONE NUMBER _____

FACSIMILE NUMBER _____

EMAIL ADDRESS _____

FEDERAL TAX I.D. #

DATE SUBMITTED

FOR THE CONSTRUCTION OF:

**LYONS ROAD NORTH OF LAKE WORTH DRAINAGE
DISTRICT (LWDD) L-30 CANAL TO BOYNTON BEACH
BOULEVARD & LYONS ROAD AND BOYNTON BEACH
BOULEVARD INTERSECTION IMPROVEMENTS
PALM BEACH COUNTY PROJECT NO. 2018503 & 2020110**

TO THE BOARD OF COUNTY COMMISSIONERS OF
PALM BEACH COUNTY, FLORIDA:

We, the undersigned (Contractor), hereby declare that no person or persons, firm or corporation, other than the undersigned, are interested in this Proposal as principals, and that this Proposal is made without collusion with any person, firm, or corporation, and that we are not on the Scrutinized Companies List as stated on page SC-1, and we have carefully and to our full satisfaction examined the Contract Documents, and that we have made a full examination of the location of the proposed Work and the source of supply of Materials, and we hereby agree to furnish and pay for all necessary labor, Equipment, Materials and services, fully understanding that the quantities shown herein are approximate only and that we will fully complete all Work in accordance with the Contract Documents and the requirements under them of the Engineer, within the time limit specified in this Proposal for the following unit prices, to wit:

PROPOSAL FORM

BID PROPOSAL LYONS ROAD FROM LWDD L-30 CANAL TO BOYNTON BEACH BOULEVARD and LYONS ROAD AND BOYNTON BEACH BOULEVARD INTERSECTION IMPROVEMENTS CONTRACT PBC PROJECT # 2018503 & 2020110						
#	FDOT ITEM NUMBER	ITEM DESCRIPTION	QTY	UNITS	UNIT PRICE	AMOUNT
ROADWAY ITEMS						
1	0101 1	Mobilization	1	LS		
2	0102 1	Maintenance of Traffic (Including Ped. MOT)	1	LS		
3	0110 1 1	Clearing and Grubbing	1	LS		
4	104 11	Floating Turbidity Barrier	1,200	LF		
5	0104 18	Inlet Protection System	84	EA		
6	0120 1	Regular Excavation	22,865	CY		
7	0120 6	Embankment (Compacted In Place)	2,062	CY		
8	N/A	Canal Excavation	287	CY		
9	N/A	Canal Embankment(Compacted In Place)	359	CY		
10	0285 713	Optional Base, Base Group 13	38,274	SY		
11	0285 713	Optional Base, Base Group 2	55	SY		
12	0327 70 1	Mill Existing Asphalt Pavement, 1" Avg Depth	114,091	SY		
13	0334 1 13	Superpave Asphalt Concrete (Traffic C)(1.5")	4,970.18	TN		
14	0337 7 82	Asphalt Concrete Friction Course (1.0") (FC-9.5)	8,719.88	TN		
15	0339 1	Miscellaneous Asphalt Pavement	101.7	TN		
16	0400 4 1	Concrete Class IV, Culverts	78.4	CY		
17	0415 1 1	Reinforcing Steel-Roadway	15,390	LB		
18	0425 1351	Inlets (Curb) '(Type P-5) (<10')	8	EA		
19	0425 1355	Inlets (Curb) (Type P-5) (Partial)	12	EA		
20	0425 1361	Inlets (Curb) (Type P-6) (<10')	3	EA		
21	0425 1365	Inlets (Curb) (Type P-6) (Partial)	19	EA		
22	0425 1525	Inlets (Ditch Bottom) (Type C) (Partial)	1	EA		
23	0425 1545	Inlets (Ditch Bottom) (Type D) (Partial)	3	EA		
24	0425 2 41	Manholes (Type P-7) (10')	1	EA		
25	0425 2 43	Manhole Type P-7 (Partial)	7	EA		
26	0425 4	Adjust Inlets	3	EA		
27	425 5	Adjust Drainage Manhole	4	EA		
28	N/A	Yard Drain	19	EA		
29	0430 17 4118	18" Pipe Culvert, Round	80	LF		
30	0430 17 5112	Pipe Culvert (12")	112	LF		
31	0430 17 5118	Pipe Culvert (18" S/CD)	102	LF		
32	N/A	Storm Sewer Pumping (Exist.) (24" or Less) (See Sp's)	8,259	LF		
33	N/A	Storm Sewer Pumping (Exist.) (>24" to 48") (See Sp's)	7,292	LF		
34	0443 70 3	French Drain, 18" Pipe	370	LF		
35	0520 1 10	Concrete Curb & Gutter (Type F)	42,812	LF		
36	N/A	Engraving of Curb Face (See Sp's)	8	EA		
37	N/A	Color Treated Stamped Concrete	923	SY		
38	0522 1	Concrete Sidewalk (4" Thick)	1,046	SY		
39	0522 2	Concrete Sidewalk & Driveway (6" Thick)	581	SY		
40	0570 1 2	Sodding	40,782	SY		
41	0530 3 3	Riprap, Rubble, Bank and Shore	142	TN		
42	0536 1 1	Guardrail - Roadway	4,100	LF		
43	0536-6	Pipe Rail for Guardrail	1,300	LF		
44	0536 85 20	Guardrail End Treatment-Trailing Anchorage	2	EA		
45	0536 85 24	Guardrail End Treatment-Parallel Approach Terminal	2	EA		
46	0630 2 11 2A	2 - 2" PVC Conduits (Sch 40) (Open Trench)	10,019	LF		
47	0630 2 12 2 2	2 - 2" PVC Conduits (Sch 40) (Directional Bore)	1,555	LF		

PROPOSAL FORM

BID PROPOSAL LYONS ROAD FROM LWDD L-30 CANAL TO BOYNTON BEACH BOULEVARD and LYONS ROAD AND BOYNTON BEACH BOULEVARD INTERSECTION IMPROVEMENTS CONTRACT PBC PROJECT # 2018503 & 2020110						
#	FDOT ITEM NUMBER	ITEM DESCRIPTION	QTY	UNITS	UNIT PRICE	AMOUNT
48	633-1-121	Fiber Optic Cable (F&I) (Underground) (2-12 FSM Fibres)	1,000	LF		
49	0633 1122	Fiber Optic Cable (F&I) (Underground) (13-48 Fibers)	18,300	LF		
50	633-2-31	Fiber Optic Connection (Install) (Splice)	5	EA		
51	633-3-12	Fiber Optic Connection Hardware (F&I) (Splice Tray)	5	EA		
52	0635-2-11	Pull Box (Small) (17" x 30" x 24"D)	17	EA		
53	0635-2-15	Pull Box (Large) (30" x 48" x 24"D)	9	EA		
54	0646-1-40	ALUMINUM SIGNALS POLE, RELOCATE	2	EA		
55	0676 2300	ITS Cabinet (Hub) (Provide & Install)	1	EA		
SUBTOTAL (ROADWAY)						
UTILITY ADJUSTMENT						
56	N/A	Construction Survey	1	LS		
57	N/A	Furnish and Install 16" DIP Water Main	740	LF		
58	N/A	Furnish and Install 16" DIP Wastewater Force Main	150	LF		
59	N/A	Furnish and Install 16" Megalug Mechanical Joint Restraint	242	EA		
60	N/A	Furnish and Install Ductile Iron Fittings for Water Main	14.30	TN		
61	N/A	Furnish and Install Ductile Iron Fittings for Wastewater Forcemain	1.36	TN		
62	N/A	Removal and Disposal of Existing 16" DIP Water Main	511	LF		
63	N/A	Removal and Disposal of Existing 16" PVC Wastewater Force Main	139	LF		
64	N/A	16" Diameter Connection to Existing Water Main or Wastewater Force include Restraining	38	EA		
65	N/A	16" Existing Pipe Bell Joint Restraint Harness	38	EA		
66	N/A	16" Joint Restraint Gasket DIP(Field Lock or Grip)	92	EA		
67	N/A	Sample Point	34	EA		
68	N/A	Adjustment of Air Release Valve Manhole	8	EA		
69	N/A	Furnish and Install Fire Hydrant Assembly	1	EA		
70	N/A	Asphat Pavement Restoration	124	SY		
71	N/A	Wastewater Forcemain Temporary Bypass (16") with 2 Line Stops(Installation and Removal)	1	LS		
72	N/A	Record Drawings	1	LS		
73	N/A	Preconstruction Video Taping	1	LS		
74	N/A	Density Tests	76	EA		
75	N/A	Proctor Tests	38	EA		
SUBTOTAL (UTILITIES)						
CONTINGENCY ITEMS						
76	0102 14	Traffic Control Officer (Non MOT)	60	HR		
77	0102 99	Changeable (Variable Message) Sign (Non MOT)	11	ED		
78	0121 70	Flowable Fill	72	CY		
79	N/A	Storm Sewer Cleaning(Exist.) (24" or Less)(See Sp's)	8,269	LF		
80	N/A	Storm Sewer Cleaning(Exist.) (>24" to 48")(See Sp's)	7,292	LF		
81	N/A	Box Culvert Cleaning (Exist.) (10' x 6')	98	LF		
82	N/A	Support Existing Utilities During Proposed Utilities/Drainage Installation	700	LF		
83	N/A	Valve Box Replacement and Adjustment	104	EA		

PROPOSAL FORM

BID PROPOSAL LYONS ROAD FROM LWDD L-30 CANAL TO BOYNTON BEACH BOULEVARD and LYONS ROAD AND BOYNTON BEACH BOULEVARD INTERSECTION IMPROVEMENTS CONTRACT PBC PROJECT # 2018503 & 2020110						
#	FDOT ITEM NUMBER	ITEM DESCRIPTION	QTY	UNITS	UNIT PRICE	AMOUNT
84	N/A	Single Line Stop (16")	19	EA		
85	N/A	Relocation or Adjustment of Existing Fire Hydrant	19	EA		
86	N/A	Gate Valve and Box (16")	2	EA		
87	N/A	Butterfly Valve and Box(16")	5	EA		
SUBTOTAL (CONTINGENCY)						
SIGNALIZATION ITEMS						
88	630-2-11-2A	Additional 2" PVC (Sch 40) Conduit (In Open Trench)	175	LF		
89	630-2-12-2-2	2-2" (HDPE SDR 11) Under Pavement Conduit (Directional Bore)	234	LF		
90	630-2-12-2-4	4-2" (HDPE SDR 11) Under Pavement Conduit (Directional Bore)	400	LF		
91	630-2-12-2-7	7-2" (HDPE SDR 11) UNDER PAVEMENT CONDUIT (DIRECTIONAL BORE)	305	LF		
92	630-2-14-1	1" RIGID CONDUIT HOT DIPPED GALVANIZED CONDUIT SURFACE MOUNTED	120	LF		
93	632-7-1-7	SIGNAL CABLE- 7 CONDUCTOR	1	PI		
94	632-7-1-7A	PEDESTRIAN SIGNAL CABLE- 7 CONDUCTOR	1	PI		
95	632-7-1-19	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	1	PI		
96	632-7-4	Signal Cable (Adjust)	1	PI		
97	632-7-6	Signal Cable, Remove - In Intersection, adjust	2	PI		
98	635-2-12-A	Pull Box (17" x 30" x 12"D) Heavy Duty Covers (Tier 22)	27	EA		
99	639-1-121	Electrical Power Service (F&I) (Underground) Meter Furnished By Power Company	2	AS		
100	639-2-1-3	ELECTRICAL SERVICE WIRE (SIGLE PHASE 3-WIRE, TRIPLEX)	120	LF		
101	639-3-11	Electrical Service Disconnect (F&I) Pole Mount	1	EA		
102	641-1-12-16	Prestressed Concrete Pole, F&I, 16' Type P-II Service Pole	2	EA		
103	641-2-80	Concrete Pole Removal - Deep (Includes Pole And Complete Removal of the Pole Foundation Depth of Up To 25 Feet) Includes Disposal of Pole When Instructed by Engineer	3	EA		
104	646-1-11	Aluminum Signals Pole, Pedestal	3	EA		
105	646-1-12	ALUMINUM SIGNALS POLE, FURNISH & INSTALL PEDESTRIAN DETECTOR POST	4	EA		
106	646-1-60	Aluminum Signals Pole, Remove	7	EA		
107	649-22-1L	Mast Arm Assembly with Street Light, Furnish and Install On Existing Foundation, Single Arm 30' (A30/S-P1/S/L)	1	EA		
108	649-22-6	MAST ARM ASSEMBLY , FURNISH AND INSTALL ON EXISTING FOUNDATION, SINGLE ARM 50' (A50/S-P3/S)	1	EA		
109	649-22-6L	Mast Arm Assembly with Street Light, Furnish and Install On Existing Foundation, Single Arm 50' (A50/S-P3/S/L)	1	EA		

PROPOSAL FORM

BID PROPOSAL LYONS ROAD FROM LWDD L-30 CANAL TO BOYNTON BEACH BOULEVARD and LYONS ROAD AND BOYNTON BEACH BOULEVARD INTERSECTION IMPROVEMENTS CONTRACT PBC PROJECT # 2018503 & 2020110						
#	FDOT ITEM NUMBER	ITEM DESCRIPTION	QTY	UNITS	UNIT PRICE	AMOUNT
110	649-22-21-HD	MAST ARM ASSEMBLY , FURNISH AND INSTALL ON EXISTING FOUNDATION, SINGLE ARM 78' HEAVY DUTY(A78/S-P6/S-HD)	1	EA		
111	649-22-21L-HD	Mast Arm Assembly with Street Light, Furnish and Install On Existing Foundation, Single Arm 78' Heavy Duty (A78/S-P6/S/L-HD)	1	EA		
112	649-2-12-40	Drilled Shaft Foundation Assembly, 12' Deep and 4.0' Diameter, Furnish and Install (Ds/12/4.0)	1	EA		
113	649-2-12-45	Drilled Shaft Foundation Assembly, 12' Deep and 4.5' Diameter, Furnish and Install (Ds/12/4.5)	1	EA		
114	649-2-16-45	Drilled Shaft Foundation Assembly, 16' Deep and 4.5' Diameter, Furnish and Install (DS/16/4.5)	1	EA		
115	649-2-18-45	Drilled Shaft Foundation Assembly, 18' Deep and 4.5' Diameter, Furnish and Install (DS/18/4.5)	1	EA		
116	649-2-20-50	Drilled Shaft Foundation Assembly, 20' Deep and 5.0' Diameter, Furnish and Install (DS/20/5.0)	2	EA		
117	649-2-20-50-AD	Additional Depth for Drilled Shaft Foundation Assembly, 20' Deep and 5.0' Diameter, Furnish and Install (DS/20/5.0)	12	LF		
118	649-26-05	STEEL MAST ARM ASSEMBLY , REMOVE, DEEP FOUNDATION - BOLT ON ATTACHMENT	2	EA		
119	650-1-13	Vehicular Traffic Signal, Furnish & Install, Aluminum, 3 Section, 1 Way	11	AS		
120	650-1-14	Vehicular Traffic Signal, Furnish & Install Aluminum, 4 Section, 1 Way	2	AS		
121	650-1-15	Vehicular Traffic Signal, Furnish & Install Aluminum, 5 Section, 1 Way	1	AS		
122	650-1-60	TRAFFIC SIGNAL HEAD ASSEMBLY, REMOVAL	5	EA		
123	653-191	Pedestrian Signal - Count Down (1-Way) Aluminum	6	EA		
124	653-192	Pedestrian Signal - Count Down (2-Way) Aluminum	3	EA		
125	653-1-60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL	4	EA		
126	660-1-109	Loop Detector Inductive, F&I, Type 9	42	EA		
127	660-2-106-B	Loop Assembly (Type F - 46')	42	EA		
128	660-4-60	VEHICLE DETECTION SYSTEM - VIDEO, REMOVE	8	EA		
129	665-1-11	Pedestrian Detector, Furnish & Install, Standard	8	EA		
130	690-80	Remove Span Wire Assembly	1	PI		
131	700-5-21	INTERNALLY ILLUMINATED SIGN (6'), LED	1	EA		
132	700-5-22	Internally Illuminated Sign (8') Fluorescent	3	EA		
133	715-11-211-L1	Furnish And Install 168 Watt Cobra Head LED Luminaire	1	EA		
134	715-680000	Light Pole Relocate	1	EA		
135	715-11-211-L2	Furnish And Install 263 Watt Cobra Head LED Luminaire	3	EA		
SUBTOTAL (SIGNALIZATION)						
TOTAL BID						

PROPOSAL FORM

BID PROPOSAL						
LYONS ROAD FROM LWDD L-30 CANAL TO BOYNTON BEACH BOULEVARD and						
LYONS ROAD AND BOYNTON BEACH BOULEVARD INTERSECTION IMPROVEMENTS						
CONTRACT						
PBC PROJECT # 2018503 & 2020110						
#	FDOT ITEM NUMBER	ITEM DESCRIPTION	QTY	UNITS	UNIT PRICE	AMOUNT
THE COUNTY DOES NOT GUARANTEE THE ACCURACY OF THE FORMULAS AND EXTENSIONS USED IN THIS SPREADSHEET.						
THE ITEMS AND QUANTITIES ABOVE, SHALL GOVERN OVER THE PLANS.						
PAY ITEM FOOTNOTES IN CONSTRUCTION PLANS SHALL ALSO BE INCLUDED IN ITEM UNIT PRICE.						
Note #	FDOT Item #	PAY ITEM FOOTNOTES				
1	All	All costs for Maintenance of Traffic (MOT) and mobilization shall be considered incidental to, and shall be included in, unit prices for the pay items.				
2	All	All items shall include cost to furnish and install unless otherwise noted.				
3	All	FDOT Item numbers are for reference only.				
4	0110 1 1	Removal of Median Trees & Small Plant Material shall be included in this item. Selective Removal.				

PROPOSAL FORM

PROJECT NO. 2018503 & 2020110

TOTAL BID

\$

IN FIGURES

The Contractor acknowledges that Addenda _____ thru _____ have been received and that related costs are reflected in the submitted bid. Contractor has committed to _____% ***SBE participation*** as set forth on the Schedule 1 and Schedule 2 that are completed and submitted by Contractor. Contractor shall comply with said goal if awarded the Contract.

The Contractor hereby certifies and agrees that the following information is correct: In preparing its response to the Solicitation, the Contractor has considered all proposals submitted from qualified, potential Subcontractors and suppliers, and has not engaged in "discrimination" as defined in the County's Commercial Nondiscrimination Policy as set forth in Resolution R2025-0748 as amended, to wit: discrimination in the solicitation, selection or commercial treatment of any Subcontractor, vendor, supplier or commercial customer on the basis of race, color, national origin, religion, ancestry, sex, age, marital status, familial status, sexual orientation, disability, or genetic information, or on the basis of any otherwise unlawful use of characteristics regarding the vendor's, supplier's or commercial customer's employees or owners; provided that nothing in this policy shall be construed to prohibit or limit otherwise lawful efforts to remedy the effects of discrimination that have occurred or are occurring in the County's relevant marketplace of Palm Beach County. Without limiting the foregoing, "discrimination" also includes retaliating against any person or other entity for reporting any incident of "discrimination." Without limiting any other provision of the solicitation, it is understood and agreed that, if this certification is false, such false certification will constitute grounds for the County to reject the proposal submitted by the Contractor for this Solicitation, and to terminate any contract awarded based on the response. As part of its proposal, the Contractor shall provide to the County a list of all instances within the immediate past four (4) years where there has been a final adjudicated determination in a legal or administrative proceeding in the State of Florida that the Contractor discriminated against its Subcontractors, vendors, suppliers or commercial customers, and a description of the status or resolution of that complaint, including any remedial action taken. As a condition of submitting a proposal to the County, the Contractor agrees to comply with the County's Commercial Nondiscrimination Policy as described in Resolution R2025-0748, as amended.

The Contractor further agrees to perform all force account Work, as provided for in the General Provisions, and to execute the Contract and return to the County, along with a Contract Bond and Certificate of Insurance within fourteen (14) Working Days of the date of the Letter of Intent to Award and to commence Work with adequate forces and Equipment within fourteen (14) Calendar Days of the date set forth in the Notice to Proceed and to fully complete all contracted Work under the same in accordance with Contract Documents within the Contract Time.

PROPOSAL FORM

THE TIMELY COMPLETION OF THIS PROJECT IS CRITICAL TO THE HEALTH, SAFETY AND WELFARE OF THE TRAVELING PUBLIC. It is the desire of Palm Beach County to expedite the construction and opening to traffic of the project. The Contractor shall be required to work such hours, weekends and/or Holidays to meet the required Contract schedules.

The Contractor shall complete in full all Work under this Contract within not more than eight hundred twenty day [820]*) Calendar Days (Contract Time). It is further agreed that should the Contractor fail to complete all Work under this Contract within the Contract Time; then, due to the criticalness of the timely completion of this project, liquidated damages for failure to meet these provisions shall be in accordance with Section 8 of the General Provisions.

The Contractor further agrees to furnish a sufficient and satisfactory Bond, on the form herein provided, in the sum of not less than 100% of the Contract price of the Work as indicated by the approximate quantities shown herein.

The Contractor further agrees to bear the full cost of maintaining all Work until the final acceptance, as provided in the Contract Documents.

Accompanying this Proposal is a Proposal Guaranty (Bid Bond) made payable to Palm Beach County, a Political Subdivision of the State of Florida, in the sum of 5% of amount Bid which is to be forfeited as liquidated damages if, in case this Proposal is accepted, the undersigned should fail to execute the attached Contract under the conditions of this Proposal. Otherwise, the Bid Bond is to be returned to the Contractor upon the delivery of a satisfactory Contract Bond.

Company Name:	_____	Authorized Officer:	_____
			(Print)
Address:	_____	Signature:	_____

PROPOSAL FORM

CONTRACTOR CERTIFICATION

PALM BEACH COUNTY

ENGINEERING AND PUBLIC WORKS DEPARTMENT

NPDES GENERAL PERMIT FOR STORM WATER DISCHARGES

FROM

ROADWAY CONSTRUCTION SITES

Lyons Road from LWDD L-30 Canal to Boynton Beach Boulevard, Lyons Road and Boynton
Beach Boulevard Intersection Improvements

PALM BEACH COUNTY PROJECT NO. 2018503 & 2020110

“I certify under penalty of law that I understand the terms and conditions of the general National Pollutant Discharge Elimination System (NPDES) permit that authorizes the storm water discharges associated with industrial activity from the construction site identified as part of this certification.”

Name of Contracting Firm: _____

By: _____ Date: _____

Name and Title: _____

Address or P.O. Box: _____

City State Zip Code

Telephone: _____
Area Code Number